

Contract

GLASGOW HARBOUR - LOT 1

Provision of new road and drainage infrastructure to service new development of over 600 flats at Glasgow Waterfront. This includes installation of 400m of large diameter concrete surface water system at a depth of approximately 6m below finished ground level and 400m of Foul Water drainage system. Roadworks include approx 3000sq metres of new carriageway with 1200sq metres of reclaimed granite and whin setts laid to new car parking areas. Civils works are also being carried out for installation of services to the new plots with close liaison being required with the three number Building Contractors who are constructing the new development.



Employer

Glasgow Harbour Ltd

Completion

August 2004

Engineer

Arup Scotland

Value

£2m